



# FCX - AX SERIES ABSOLUTE PRESSURE TRANSMITTER

DATA SHEET FHA, FKA---3

The FCX-AX absolute pressure transmitter accurately measures absolute pressure and transmits a proportional 4 to 20mA signal.

The transmitter utilizes a unique micromachined capacitance silicon sensor with state-of-the-art microprocessor tech-nology to provide exceptional performance and functionality.



#### 1. High accuracy

0.2% accuracy for all calibrated spans is a standard feature for all AP models covering 1.6kPa{0.016bar} range to 3000kPa{30bar} high pressure range. 0.1% accuracy is available as option. Fuji's micro-capacitance silicon sensor assures this accuracy for all suppressed calibration ranges without additional adjustment.

#### 2. Minimum environmental influence

The "Advanced Floating Cell" design which protects the pressure sensor against changes in temperature, and overpressure substantially reduces total measurement error in actual field applications.

#### 3. Replaceable Communication Module

Fuji micro-electronics manufacturing technology offers replaceable communication module that makes FCX – AX transmitter very unique in design. In case of change in communication protocol, all that needs to be done is just to replace the module and the transmitter gets upgraded to the new version.

#### 4. Fuji/HART bilingual communication module

The communication module is "bilingual" to speak both Fuji proprietary protocol and HART. Any HART compatible devices can communicate with FCX – AX series transmitters.

#### 5. Application flexibility

Various options that render the FCX-AX suitable for almost any process applications include:

- Analog indicator at either the electronics side or terminal side
- Full range of hazardous area approvals
- Built-in RFI filter and lightning arrester
- $4\frac{1}{2}$ -digits LCD meter
- Stainless steel electronics housing
- Wide selection of materials

#### Burnout current flexibility (Under Scale: 3.2 to 3.8mA, Over Scale: 20.8 to 21.6mA)

Burnout signal level is adjustable using Model FXW hand Held Communicator (HHC) to comply with NAMUR NE43. (Available for amplifier unit from version 24 and FXW(HHC) version 5.3.)

#### 7. Dry calibration without reference pressure

Thanks to the best combination of unique construction of mechanical parts (Sensor unit) and high performance electronics circuit (Electronics unit), reliability of dry calibration without reference pressure is at equal level as wet calibration.



## **SPECIFICATIONS**

### **Functional specifications**

Type:

Model FHA: 4 to 20mA

Model FKA: 4 to 20mA with digital signal

Service: Liquid, gas, or vapour Span, range, and overrange limit:

	Span limit [kPa abs] {bar abs}			Range limit	Overrange limit
Type	Min.		Max.	[kPa abs] {bar abs}	[MPa] {bar}
	FHA	FKA	FHA/FKA		
F□A□01	1.6	1.6	16	0 to +16	0.5
F□A□02	{0.016} 13	{0.016} 1.6	{0.16} 130	{0 to +0.16} 0 to +130	(5) 0.5
F□A□03	{0.13} 50	{0.016} 5	{1.3} 500	{0 to +1.3} 0 to +500	(5) 1.5
F□A□04	{0.5} 300 {3}	{0.05} 30 {0.3}	{5} 3000 {30}	{0 to +5} 0 to +3000 {0 to +30}	{15} 9 {90}

Remark: To minimize environmental influence, span should be greater than 1/40 of the max. span in most applications.

 The maximum span of each sensor can be converted to different units using factors as below.

1MPa abs=10<sup>3</sup>kPa abs=10bar abs=10.19716kgf/cm<sup>2</sup> abs =145.0377psi abs

1kPa abs=10mbar abs=101.9716mm $H_2O$  abs= 4.01463in $H_2O$  abs=7.50062mm $H_2O$  abs

Output signal:

Model FHA: 4 to 20mA DC 2-wire

Model FKA: 4 to 20mA DC with digital signal super-

imposed on the 4 to 20mA signal.


**Power supply:** Transmitter operates on 10.5V to 45V DC

at transmitter terminals.

10.5V to 32V DC for the units with op-

tional arrester.

Load limitations: see figure below



Note: For communication with HHC (Model: FXW), min. of  $250\Omega$  is required.

#### Hazardous locations: (Approval pending)

Authorities	Flameproof	Intrinsic safety	Type N Nonincendive
BASEEFA	Ex ds IIC T5, T6	EEx ia IIC T4, T5	Ex N II T5
Factory	Class I II III	Class I II III	Class I II III
Mutual	Div. 1	Div. 1	Div. 2
CSA	Groups B thru. G	Groups A thru. F	Groups A thru. G
	Class I II III	Class I II III	Class I II III
	Div. 1	Div. 1	Div. 2
RIIS SAA	Groups C thru. G Ex ds IIB+H <sub>2</sub> T4 Ex d II C T5, T6 IP 66/67	Groups A thru. G — Ex ia II C T5, T6 IP 66/67	Groups A thru. G — Ex n II C T5, T6 IP 66/67

#### Zero/span adjustment:

Model FHA: Zero is adjustable from the external

adjustment screw.

The adjustment screw can also function to adjust span when MODE SWITCH (located on the electronics unit) is in the span mode. INHIBIT mode to disable the adjustment screw is also available.

Model FKA: Zero and span are adjustable from the HHC. Zero is also adjustable externally

from the adjustment screw.

Damping: Adjustable electrical damping

Model FHA: The time constant is adjustable to 0, 0.3,

1.2, 4.8, or 19.2 seconds.

Model FKA: The time constant is adjustable between

0 to 38.4 seconds. (9 steps)

Zero elevation/suppression:

Zero can be elevated within the specified

range limit of each sensor model.

Normal/reverse action:

Model FHA: Selectable by moving a jumper pin located

on the electronics unit.

Model FKA: Configurable from HHC.

Indication: Analog indicator or  $4\frac{1}{2}$ -digit LCD meter,

as specified.

Burnout direction: If self-diagnostic detect transmitter failure, the analog signal will be driven to ei-

ther "Output Hold", "Output Overscale" or "Output Underscale" modes.

Model FHA: Unless otherwise specified in the order,

the transmitter will be shipped in "Output Hold" mode.

(Output signal just before failure happens

is maintained.)

Model FKA: Selectable from HHC

"Output Hold"

Output signal is hold as the value just before failure happens. "Output Overscale":

Approx. 21.6mA

(Adjustable within the range 20.8mA to


21.6mA from HHC)

"Output Underscale":

Approx. 3.8mA

(Adjustable within the range 3.2mA to

3.8mA from HHC)



#### Loop-check output:

Model FHA: Transmitter can output constant signal of

4mA, 12mA, or 20mA if MODE SWITCH

is set to the loop check mode.

Model FKA: Transmitter can be configured to provide

constant signal 3.8mA through 21.6mA

by HHC.

Temperature limit: Ambient: -40 to +85°C

(-20 to +80°C for LCD indicator) (-40 to +60°C for arrester option) For explosionproof units (flameproof or intrinsic safety), ambient temperature must be within the limits specified by each standard.

Process: -40 to +85°C for silicone fill

sensor

Storage: -40 to +90°C

**Humidity limit:** O to 100% RH **Communication:** (Model FKA only)

With HHC (Model FXW, consult Data Sheet No. EDS8-47), following information can be remotely displayed or recon-

figured.

Items	Display	Set
Tag No.	V	V
Model No.	V	V
Serial No.	V	_
Engineering unit	V	V
Range limit	V	_
Measuring range	V	V
Damping	V	V
Output mode	V	V
Burnout direction	V	V
Adjustment	V	V
Output adjust	_	V
Data	V	_
Self diagnoses	V	_
Printer	_	_
External switch lock	V	V
Transmitter display(*)	V	V

Note: (\*) HHC's version must be more than 5.0 (or FXW  $\square\square\square\square1-\square2$ ), to use this function.

#### Performance specifications

Accuracy rating: (including linearity, hysteresis, and repeatability).

(Standard)

For spans greater than 1/10 of URL:  $\pm 0.2\%$  of span For spans below 1/10 of URL (Model FKA only):

$$\pm$$
 (0.1 + 0.1  $\frac{0.1 \times URL}{Span}$  )% of span

(Option)

(Not available for Max span 16kPa abs, 130kPa abs) For spans greater than 1/10 of URL:  $\pm 0.1\%$  of span For spans below 1/10 of URL (Model FKA only):

 $\pm$  (0.05 + 0.05  $\frac{0.1 \times \text{URL}}{\text{Span}}$  )% of span

Linearity: 0.1% of calibrated span

Stability:  $\pm 0.2\%$  of upper range limit (URL) for 24

months

Temperature effect:

Effect per 28°C change between the

limits of  $-40^{\circ}\text{C}$  and  $+85^{\circ}\text{C}$ 

Zero shift:  $\pm (0.125+0.1 \frac{URL}{Span})\%$ 

Total effect: ±(0.15+0.1 URL Span )%

Double the effects for material code (7th digit in code symbols) "H", "M", and "T".

Overrange effect: Zero shift; 0.2% of URL for any overrange

to maximum limit

Supply voltage effect:

Less than 0.05% of calibrated span per

10V

RFI effect: Less than 0.2% of URL for the frequen-

cies of 20 to 1000MHz and field strength 30V/m when electronics covers on. (Classification: 2-abc: 0.2% span per

SAMA PMC 33.1)
Step response: Time constant. 0.2 s

Dead time: approximately 0.3 s (without electrical damping)

Mounting position effect:

Zero shift, less than 0.1kPa{1mbar} for a

10° tilt in any plane.

No effect on span. This error can be cor-

rected by adjusting zero.

Dielectric strength:

500V AC, 50/60Hz 1 min., between circuit

and earth.

Insulation resistance:

More than 100M  $\!\Omega\!$  at 500V DC.

Turn-on time: 4 sec

Internal resistance for external field indicator:

 $12\Omega$  or less

#### Physical specifications

Electrical connections:

G1/2, 1/2-14NPT, Pg13.5, or M20 x 1.5 conduit, as specified.

Process connections:

1/4-18 NPT or Rc1/4, as specified.

Process-wetted parts material:

Material code (7th digit in "Code symbols")	Process cover	Diaphragm	Wetted sensor body	Vent/drain
V	316	316L	316	316
Н	stainless steel 316	stainless steel Hastelloy-C	stainless steel Hastelloy-C	stainless steel 316
М	stainless steel 316	Monel	lining Monel lining	stainless steel 316
Т	stainless steel 316 stainless steel	Tantalum	Tantalum lining	stainless steel 316 stainless steel

Notes: Sensor O-rings: Viton

Availability of above material design depends on ranges.

Refer to "Code symbols".

#### Non-wetted parts material:

Electronics housing: Low copper die-cast aluminum alloy (standard), finished with polyester coating, or 316 stainless steel (SCS14 per JIS G5121), as

specified.

Bolts and nut: Cr-Mo alloy (standard) or

304 stainless steel Fill fluid: Silicone oil

Mounting bracket: Carbon steel with epoxy coating or 304 stainless steel,

as specified

Environmental protection:

IEC IP67 and NEMA 4X

Mounting: On 60.5mm (JIS 50A) pipe using mounting

bracket, direct wall mounting, or direct

process mounting.

Mass{weight}: Transmitter approximately 3.4kg without

options.

Add; 0.5kg for mounting bracket 0.8kg for indicator option

4.5kg for stainless steel housing

option

### Optional features

**Indicator:** A plug-in analog indicator (1.5% accuracy)

can be housed in the electronics compartment or in the terminal box of the housing. An optional  $4\frac{1}{2}$  digits LCD meter is also

available.

Arrester: A built-in arrester protects the electronics

from lightning surges. Lightning surge immunity:

 $4KV (1.2 \times 50 \mu s)$ 

Degreasing: Process-wetted parts are cleaned, but the

fill fluid is standard silicone oil. Not for use on oxygen or chlorine measurement.

NACE specification:

Metallic materials for all pressure boundary parts comply with NACE MR-01-75. 304 stainless steel bolts and nuts, ASTM B7M or L7M bolts and 2HM nuts (Class

II) are available.

Customer tag: A stainless steel tag for customer tag data

is wired to the transmitter.

Coating of cell: Cell's surface is finished with epoxy/

polyurethane double coating. Specify if environment is extremely corrosive.

# **ACCESSORIES**

Oval flanges: (Model FFP, refer to Data Sheet No.

EDS6-10

Converts process connection to 1/2-14 NPT or to Rc1/2; in carbon steel or in 316 stainless steel.

Hand held communicator:

(Model FXW, refer to Data Sheet No.EDS

8-47)

Communication module: (Standard for model FKA)

By adding communication module, remote setting function becomes available for EHA

able for FHA.

Remark: When the communication module is connected, the operation mode of external zero/span adjustment screw is limited to zero adjustment only.

# **CODE SYMBOLS**

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15						
0 3 -	Description					
FHA FKA	Type  4 to 20mA, Output type  4 to 20mA with digital signal, Output type					
	Connections					
	Process connection	Oval f screw	0	Condu		
S T V	Rc1/4 1/4-18NPT 1/4-18NPT 1/4-18NPT 1/4-18NPT	7/16-2 M10 M10	20UNF 20UNF 20UNF	G 1/2 1/2-14 Pg 13. M20 × Pg 13.	5 1.5	
	Span limit					
	Span limit FHA/FKA [kPa abs]{bar abs}(*		Process cove	r	Diaphragm	Wetted cell body
1V1H1M	1.6/1.616/16 {0.016/0.0160.16	/0.16	316 stainless 316 stainless 316 stainless	steel	316L stainless steel Hast. C Monel	316 stainless steel Hast. C lining Monel lining
2V	13/1.6130/130 {0.13/0.0161.3/1.	3}	316 stainless 316 stainless 316 stainless 316 stainless	steel steel	316L stainless steel Hast. C Monel Tantalum	316 stainless steel Hast. C lining Monel lining Tantalum lining
3V3H3H3H3H	50/5500/500 {0.5/0.055/5}		316 stainless 316 stainless 316 stainless 316 stainless	steel steel	316L stainlesssteel Hast. C Monel Tantalum	316 stainless steel Hast. C lining Monel lining Tantalum lining
4V	300/303000/3000	)	316stainless 316stainless 316 stainless 316 stainless	steel steel	316L stainless steel Hast. C Monel Tantalum	316 stainless steel Hast. C lining Monel lining Tantalum lining

Note: \* 100: 1 turn down is possible for model FKA, but should be used at a span greater than 1/40 of the maximum span for better performance.

The product conforms to the requirements of the Electromagnetic compatibility Directive 89/336/EEC as detailed within the technical construction file number TN510412. The applicable standards used to demonstrate compliance are :-

EMI (Emission) EN50081-1: 1992

Test item	Frequency range	Basic standard
Applicable Electro- magnetic Radiation Disturbance	30-1000MHz	EN55022 Class B

EMS (Immunity) EN50082-1:1992


No.	Test item	Test specification	Basic standard	Performance criteria
1	Electrostatic discharge	8kV (Air)	IEC 801-2:1984	В
2	Radio-frequency electromagnetic field.	27-500MHz 3V/m (Unmodulated)	IEC 801-3:1984	А
3	Fast transients common mode	0.5kV, 5/50 (Tr/Th) ns 5kHz Rep.	IEC 801-4:1988	В

"LVD - The transmitter is not covered by the requirements of the LVD standard."  $\label{eq:local_local_local}$ 

1 2 3 4 5 6 7 8 9 10 11 12 13 14 FHA 0 3 3 - 3 - 3 - 3 - 3 - 3 - 3 - 3 - 3 -	5	
FKA 0 3-	]	Description
	Indicator and arrester	Description
	Indicator	Arrester
A	None	None
В	Analog, 0 to 100% linear scale	None
D	Analog, custom scale	None
J	Analog, double scale	None (JIS and SI unit)
E	None	Yes
	Analog, 0 to 100% linear scale	Yes
H    K	Analog, custom scale	Yes
	Analog, double scale Digital, 0 to 100%	Yes (JIS and SI unit) None
-	Digital, custom scale	None (Model FKA only)
	Digital, 0 to 100%	Yes
s   <del> </del>	Digital, custom scale	Yes (Model FKA only)
	Approvals for hazardous location	ns (Approval pending)
A  <del>    </del>	None (for ordinary locations)	
B	JIS, Flameproof (Conduit seal)	(Available for 4th digit code "S")
[C	JIS, Flameproof (Cable gland seal)	(Available for 4th digit code "S")
D	FM, Flameproof (or explosionproof	-
E	CSA, Flameproof (or explosionproof BASEEFA, Flameproof (Conduit se	-
N	: 1	d seal) (Conduit connection G 1/2 only)
н	FM, Intrinsic safety and nonincend	·
J  <del>    </del>	CSA, Intrinsic safety and nonincen	dive
κ	CENELEC, Intrinsic safety	
P	CENELEC, Intrinsic safety and BAS	**
R	SAA Flameproof (Conduit seal)(Av	
Q T	SAA Intrinsic safety(Available for 4	-
9 1 1 1 1	Side vent/ drain and mounting b	
	:	ounting bracket
A  <u></u>	:	one
B	None Ye	es, carbon steel
		es, stainless steel
	1	one
E	;	es, carbon steel es, stainless steel
<u> </u>	Stainless steel parts	ss, stairiless steel
	· ·	ss steel elec. housing Coating of cell
Y	None None	
В	Yes None	
c	None Yes	None
<u> </u>	Yes Yes	None
M	None None	
N	Yes None Yes	Yes Yes
Ω	Yes Yes	res Yes
<del>                                      </del>	Special applications and fill fluid	
	Treatment	Fill fluid
Y  <del> </del> <del> </del>	None (standard)	Silicone oil
[G]	Degreasing	Silicone oil
N	NACE specification	Silicone oil (7th digit code "T" and 15th digit code
		"A", "B" are not available)
A	Sensor O-ring	
$\vdash$	Viton Polt/put	
	Bolt/nut  Cr-Mo alloy hexagon socket head of	cap screw/carbon steel nut
	Cr-Mo alloy hexagon bolt/nut	
	NACE bolt/nut (ASTM A193 B7M/A	A194 2HM)
	NACE bolt/nut (ASTM A320 L7M/A	194 2HM)
	304 stainless steel/304 stainless s	teel (*1)
Ĺ	1 1	

<sup>\* (1)</sup> In case of tropical use, select stainless bolts and nuts.

# **OUTLINE DIAGRAM** (Unit:mm)



Note1): Cable gland is supplied in case of flamproof packing type. ø11 cable is suitable.

# Fuji Electric Co.,Ltd.

#### **Head office**

11-2 Osaki 1-chome, Shinagawa-ku, Tokyo, 141-0032 Japan Phone: 81-3-5435-7111

http://www.fujielectric.co.jp/eng/sg/KEISOKU/welcome.htm

# Fuji Electric Instruments Co.,Ltd.

#### Sales Div. International Sales Dept.

No.1, Fuji-machi, Hino-city, Tokyo, 191-8502 Japan

Phone: 81-42-585-6201, 6202 Fax: 81-42-585-6187, 6189