

Page 1 of 2

**Qualification Data Summary:**

QV DEVICE NAME: NCP333FCT2G

Test	Sample Size	Results
Saw		
100% Visual Inspection	3 lots/ 77 units	Pass
Kerf Width Measurement	3 lots/ 77units	Pass
Backside Wall Integrity	3 lots/ 5 units	Pass
Tape and Reel		
Peel test		Pass
Electronic Map vs Skeleton verification	3 wafers	Pass
De-tape and Inspect	1 reel, 100%	Pass

Visual Inspection and pick & place electronic map verification has been performed at the ON Semiconductor SSL site to ensure all rejects will continue to be detected and removed from production.

Electrical Characteristic Summary:

Electrical characteristics are not impacted.

List of Affected Standard Parts:

Part Number	Qualification Vehicle
NCP333FCT2G	NCP333FCT2G